





**ESTIMATE ANALYSIS  
ADDITIONS RENOVATIONS**



Project Leaders

Schematic Design Phase		000's										
8/29/22		A1	B1	C1	A2	B2	C2	A	B	C	D	
	A/E Control Budget 4/4/22	New Construction			Renovated Construction			Total			Reconciled Estimate 8/8/22	
		RLB	Fennessy	Difference (A1 - B1)	RLB	Fennessy	Difference (A2 - B2)	RLB	Fennessy	Difference (A - B)		
		8/4/22	8/17/22		8/4/22	8/17/22		8/4/22	8/18/22			
<b>Site Construction Area (GSF)</b>	<b>0.0</b>	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0	
<b>II. Site Construction</b>												
<b>A. Sitework (beyond 5' of building )</b>												
<b>G10 Site Preparation</b>		\$ 959.90	\$ 403.10	556.8	\$ -	\$ -	0.0	\$ 959.90	\$ 403.10	556.8	\$ 681.50	
G1010 Site Clearing		142.6	361.9	-219.3	0.0	0.0	0.0	142.6	361.9	-219.3	252.3	
G1020 Site Demo and Relocation		757.8	0.0	757.8	0.0	0.0	0.0	757.8	0.0	757.8	378.9	
G1030 Site Earthwork		59.5	41.2	18.3	0.0	0.0	0.0	59.5	41.2	18.3	50.4	
G1040 Hazardous Waste Remediation		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
<b>G20 Site Improvements</b>		\$ 987.90	\$ 844.40	143.5	\$ -	\$ -	0.0	\$ 987.90	\$ 844.40	143.5	\$ 916.20	
G2010 Roadways		0.0	66.0	-66.0	0.0	0.0	0.0	0.0	66.0	-66.0	33.0	
G2020 Parking Lots		63.8	0.0	63.8	0.0	0.0	0.0	63.8	0.0	63.8	31.9	
G2030 Pedestrian Paving		544.1	643.0	-98.9	0.0	0.0	0.0	544.1	643.0	-98.9	593.6	
G2040 Site Development		174.8	38.2	136.6	0.0	0.0	0.0	174.8	38.2	136.6	106.5	
G2050 Landscaping		205.2	97.2	108.0	0.0	0.0	0.0	205.2	97.2	108.0	151.2	
<b>G30 Site Mechanical Utilities</b>		\$ 443.00	\$ 417.10	25.9	\$ -	\$ -	0.0	\$ 443.00	\$ 417.10	25.9	\$ 430.10	
G3010 Water Supply		45.2	417.1	-371.9	0.0	0.0	0.0	45.2	417.1	-371.9	231.2	
G3020 Sanitary Sewer		13.0	0.0	13.0	0.0	0.0	0.0	13.0	0.0	13.0	6.5	
G3030 Storm Sewer		384.8	0.0	384.8	0.0	0.0	0.0	384.8	0.0	384.8	192.4	
G3040 Heating Distribution		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
G3050 Cooling Distribution		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
G3060 Fuel Distribution		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
G3090 Other Site Mechanical Utilities		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
<b>G40 Site Electrical Utilities</b>		\$ 182.00	\$ 163.40	18.6	\$ -	\$ -	0.0	\$ 182.00	\$ 163.40	18.6	\$ 172.70	
G4010 Electrical Distribution		97.0	163.4	-66.4	0.0	0.0	0.0	97.0	163.4	-66.4	130.2	
G4020 Site Lighting		70.0	0.0	70.0	0.0	0.0	0.0	70.0	0.0	70.0	35.0	
G4030 Site Communication & Security		15.0	0.0	15.0	0.0	0.0	0.0	15.0	0.0	15.0	7.5	
G4090 Other Site Electrical Utilities		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
<b>G90 Other Site Construction</b>		\$ -	\$ -	0.0	\$ -	\$ -	0.0	\$ -	\$ -	0.0	\$ -	
G9010 Service and Pedestrian Tunnels		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
G9090 Other Site Systems and Equipment		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
<b>Total Site Construction</b>		<b>2,572.8</b>	<b>1,828.0</b>	<b>744.8</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>2,572.8</b>	<b>1,828.0</b>	<b>744.8</b>	<b>2,200.5</b>	
<b>Total Construction before Markups</b>	<b>26,900.0</b>	<b>19,265.5</b>	<b>16,472.8</b>	<b>2,792.7</b>	<b>9,616.0</b>	<b>9,574.0</b>	<b>42.0</b>	<b>28,881.5</b>	<b>26,046.8</b>	<b>2,834.7</b>	<b>27,464.6</b>	
F. Design and Pricing Contingency	included	1,912.5	1,888.1	24.4	1,101.8	1,149.3	(47.5)	0%	3,309.0	3,037.4	271.6	3,173.2
G. Performance Bond	included	450.7	357.7	93.0	259.6	217.7	41.9	0.0%	779.8	575.4	204.4	677.6
H. Insurance	included	0.0	0.0	0.0	0.0	0.0	0.0	0.0%	0.0	0.0	0.0	0.0
I. Permits (If by GC or CM)	included	0.0	0.0	0.0	0.0	0.0	0.0	0.0%	0.0	0.0	0.0	0.0
J. CM Contingency (CM Only)	included	0.0	0.0	0.0	0.0	0.0	0.0	0%	0.0	0.0	0.0	0.0
K. General Conditions	included	1,335.4	1,412.5	(77.1)	769.3	1,312.5	(543.2)	0%	2,310.5	2,725.0	(414.5)	2,517.8
L. General Requirements	included	0.0	0.0	0.0	0.0	0.0	0.0	0%	0.0	0.0	0.0	0.0
M. Overhead and Profit / Fee	included	646.7	638.5	8.2	372.6	388.6	(16.0)	0%	1,119.0	1,027.1	91.9	1,073.1
<b>Total Markups</b>	<b>0.0</b>	<b>4,345.3</b>	<b>4,296.8</b>	<b>48.5</b>	<b>2,503.3</b>	<b>3,068.1</b>	<b>(564.8)</b>	<b>7,518.3</b>	<b>7,364.9</b>	<b>153.4</b>	<b>7,441.7</b>	
<b>Construction w/Mark-ups before Escalation</b>	<b>26,900.0</b>	<b>23,610.8</b>	<b>20,769.6</b>	<b>2,841.2</b>	<b>12,119.3</b>	<b>12,642.1</b>	<b>(522.8)</b>	<b>36,399.8</b>	<b>33,411.7</b>	<b>2,988.1</b>	<b>34,906.3</b>	
<b>III. Escalation</b>	<b>Included</b>	<b>2,629.7</b>	<b>1,225.4</b>	<b>1,404.3</b>	<b>1,514.9</b>	<b>745.9</b>	<b>769.0</b>	<b>0.0%</b>	<b>4,549.9</b>	<b>1,971.3</b>	<b>2,578.6</b>	<b>3,260.6</b>
<b>Total Estimated Construction</b>	<b>\$ 26,900.0</b>	<b>\$ 26,240.5</b>	<b>\$ 21,995.0</b>	<b>\$ 4,245.5</b>	<b>\$ 13,634.2</b>	<b>\$ 13,388.0</b>	<b>\$ 246.2</b>	<b>0%</b>	<b>\$ 40,949.7</b>	<b>\$ 35,383.0</b>	<b>\$ 5,566.7</b>	<b>\$ 38,166.9</b>
<b>Variance to Budget (Over)/Under</b>		<b>659.5</b>	<b>4,905.0</b>		<b>13,265.8</b>	<b>13,512.0</b>		<b>(14,049.7)</b>	<b>(8,483.0)</b>		<b>(11,266.9)</b>	
<b>Markups %</b>		<b>22.6%</b>	<b>26.1%</b>		<b>26.0%</b>	<b>32.0%</b>		<b>26.0%</b>	<b>28.3%</b>		<b>27.1%</b>	